



PROGRESSIVE REHABILITATION PLAN

- REHABILITATE / STABILISE AND VEGETATE THE DISTURBED AREAS AFTER EACH PHASE OF WORKS (REFER TO SCHEDULE) TO ENSURE THE LAND IS STABLE (REFER TO STABILISATION NOTES).
- STABILISATION NOTES:
 - THE AREA 1 TO BE REHABILITATED / STABILISED AFTER PHASE 1 WORKS, AREA 2 TO BE REHABILITATED / STABILISED AFTER PHASE 2 WORKS AND AREA 3 TO BE REHABILITATED / STABILISED AFTER PHASE 3 WORKS.

PHASE 4 - FINAL SITE REHABILITATION WORKS

- AFTER THE ROAD HAS BEEN CONSTRUCTED (ie. AFTER PHASE 3 WORKS) KERBSIDE TURF STRIPS ARE TO BE INSTALLED IN THE LOCATIONS SHOWN IN ACCORDANCE WITH SD 6-13.
- ONCE ALL CONSTRUCTION WORKS (ie. PHASES 1 - 3) HAVE BEEN COMPLETED AND ALL AREAS 1 - 3 INCLUDING THE KERBSIDE TURF STRIPS HAVE BEEN ADEQUATELY REHABILITATED / STABILISED (REFER TO STABILISATION NOTES) THE FINAL SITE REHABILITATION WORKS SHOULD COMMENCE.
- STOCKPILE, PARKING AND MATERIAL STORAGE AREAS SHOULD BE DECOMMISSIONED.
- REHABILITATE TO ENSURE THE LAND IS STABLE (REFER TO STABILISATION NOTES).
- DIRTY WATER DIVERSION DRAINS (1) AND (2) SHOULD BE DECOMMISSIONED.
- REHABILITATE TO ENSURE THE LAND IS STABLE (REFER TO STABILISATION NOTES).
- CLEAN WATER DIVERSION DRAINS (1), (2) AND (3) AND LEVEL SPREADERS SHOULD BE DECOMMISSIONED. REHABILITATE TO ENSURE THE LAND IS STABLE (REFER TO STABILISATION NOTES).
- ONCE ALL AREAS (INCLUDING PARKING AND MATERIAL STORAGE AREA AND DIVERSION DRAINS) HAVE BEEN ADEQUATELY REHABILITATED / STABILISED (REFER TO STABILISATION NOTES) THE PIT INLET PROTECTIONS (ie. THE AGGREGATE SAUSAGES) SHOULD BE REMOVED.
- THE SEDIMENT BASIN SHOULD BE CONVERTED INTO A WATER QUALITY CONTROL POND AND THE SURROUNDING AREAS SHOULD BE SUITABLY REHABILITATED / STABILISED (REFER TO STABILISATION NOTES).
- ONCE ALL AREAS HAVE BEEN ADEQUATELY REHABILITATED / STABILISED THE BARRIER AND SEDIMENT FENCING REMAINING FOR PHASE 4 WORKS SHOULD BE REMOVED.

STABILISATION NOTES

FOR LANDS TO BE CONSIDERED SUCCESSFULLY REHABILITATED AND STABLE THE FOLLOWING GROUND COVERS MUST BE ACHIEVED:

- A MINIMUM OF 60% GRASS COVER SHOULD BE ACHIEVED WITHIN TEN WORKING DAYS FROM COMPLETION OF FORMATION; AND
- A MINIMUM OF 70% GRASS COVER SHOULD BE ACHIEVED WITHIN 2 MONTHS FROM COMPLETION OF FORMATION.

(REFER TO TABLE 1 ON DRAWING SWMP08 FOR ADDITIONAL STABILISATION NOTES AND DETAILS)

SUNSHINE COAST REGIONAL COUNCIL

CONCEPT SOIL AND WATER MANAGEMENT DIAGRAMS

Prepared by

Project No. 09000101

Sheet No. SWMP06

This drawing is subject to COPYRIGHT. The information on this drawing remains the property of SEEC Morse McVey.